



DUTY CHANGEOVER OPERATING PHILOSOPHY

NORMAL OPERATION :
RTU CONTROLS DUTY SELECTION OF PUMPS
ALTERNATING DUTY LIGHT IS ON

PUSH THE BUTTON ONCE :
RTU LOCKS DUTY SELECTION TO PUMP No 1
ALTERNATING DUTY LIGHT IS OFF

PUSH THE BUTTON A SECOND TIME :
RTU LOCKS DUTY SELECTION TO PUMP No 2
ALTERNATING DUTY LIGHT IS OFF

PUSH THE BUTTON A THIRD TIME :
SYSTEM REVERTS BACK TO NORMAL OPERATION
RTU CONTROLS DUTY SELECTION OF PUMPS
ALTERNATING DUTY LIGHT IS ON

REVISIONS	No.	DATE	DESCRIPTION	APP'D
	8	29/3/21	ADDED DUTY C/O OPERATING PHILOSOPHY & RE-DRAWN IN DGN FORMAT.	P.S.

REFERENCES	PLAN No.	DESCRIPTION	TITLE
	A1-47775	STD SPS - PUMP STN 7.5kw TO 22kw (VSD) - DIRECT METERED - I & C - DRG INDEX	

DESIGNED BY:

A.B.N. 28 065 272 942

DO NOT SCALE	GIPPSLAND WATER DRAWING STATUS	STANDARD DRAWING	GIPPSLAND WATER FACILITY CODE XXCPXX
CERTIFICATION OF COMPLIANCE WITH GIPPSLAND WATER'S DESIGN & DRAFTING REQUIREMENTS. DESIGNED: 19/04/2010 - GW/STD DRAWN: 29/03/2021 - OPT/RJ CHECKED: 31/03/2021 - P STEWART		GIPPSLAND WATER STANDARD SEWERAGE PUMP STATION PUMP STATION 7.5kw TO 22kw (VSD) - DIRECT METERED 'ACE3600' TELEMETRY SLOT 2 - 16 DI CARD ELECTRICAL SCHEMATIC DIAGRAM	
		DRAWING No. A1-47793	REV. 8